BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

Package-02 1. Improvements to Roads and Drains From Hegdenagar petrol bunk to MCECHS park in Ward No. 06 2. Improvements to Roads and Drains in Hegdenagar and Surrounding areas in Ward No. 06 3. Improvements to Roads and Drains in Munivenkatappa Layout Nagawara in Ward No. 06 4. Drilling of Borewells and Maintance in Ward No.06

SNo	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
1	976.80	Earth work excavation by manual means in ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface levelled and sides neately dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specification. As per the direction of Engineer incharge	Cum	202.92	Rupees Two Hundred Two And Paise Ninety Two Only
2	1254.72	Removing and refixing stone slabs of drains and pointing in CM (1:3) As per the direction of Engineer incharge	Sqm	80.56	Rupees Eighty And Paise Fifty Six Only
3	395.28	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 7.5cms thick As per the direction of Engineer incharge	Sqm	665.68	Rupees Six Hundred Sixty Five And Paise Sixty Eight Only
4	109.20	Providing and laying in position plain cement concrete of mix 1:3:6 with OPC cement @ 220kgs, with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5348.76	Rupees Five Thousand Three Hundred Forty Eight And Paise Seventy Six Only
5	164.00	Providing and Constructing precast concrete solid blocks with compressive strength not less than 3.5 Newton/sqm with cement mortor 1:4 masonry (quoin, jamb, closer blocks) with solid concrete blocks of size 40X15X20 cms confirming to I.S:2185/1965 in superstructure including cost of materials, labor charges, scaffolding, curing complete as per specifications	Sqm	961.42	Rupees Nine Hundred Sixty One And Paise Forty Two Only
6	84.87	Providing and constructing granite size stone masonry in foundation cement mortor 1:6, stone hammered dressed in courses not less than 20cms high, bond stones at 2m. apart in each course including cost of materaials, labour, curing complete as per specifications.	Cum	4438.22	Rupees Four Thousand Four Hundred Thirty Eight And Paise Twenty Two Only
7	188.60	Providing flush pointing to square rubble, course or uncoursed stone masonry with cement mortar 1:3, 20mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications.	Sqm	102.82	Rupees One Hundred Two And Paise Eighty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
8	36.90	Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240kgs, with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	5767.46	Rupees Five Thousand Seven Hundred Sixty Seven And Paise Forty Six Only
9	800.40	Providing granite Slabs of Selected quality roughly dressed and fixed in cement mortor (1:6) including fixing curing etc,. Complete. 10cms thick	Sqm	825.74	Rupees Eight Hundred Twenty Five And Paise Seventy Four Only
10	4658.40	Providing chamfering edges to stone slab 2.5 cms. wide as per specifications. (only chamfered length shall be recorded)	m	37.10	Rupees Thirty Seven And Paise Ten Only
11	60.00	Cement concrete pavement.Construction of un-reinforced plain cement concrete pavement, thickness as per design, over a prepared sub base with OPC cement or any other type as per clause 1051.2.2 design mix M20/M30 , with 25mm and down size graded granite metal coarse aggregates and fine aggregtes , with superplastisiser @3lts confirming to IS9103-1999 Reaffirmed-2008 , mixed in a concrete mixer of not less than 0.6 cum capacity and appropriate weigh batcher as per approved mix design, laid in approved fixed side form work (steel channel, laying and fixing of 125 micron thick polythene film, wedges, steel plates including levelling the form work as per drawing). Spreading the concrete with shovels, rackers compacted using needle, screed and plate vibrator and finished in a continuous operation including provision of contraction, expansion, construction and longitudinal joints including groove cutting charges, joint filler, separation membrane, selant primer, joint sealant, admixtures as approved, curing compound, finishing to lines and grades as per drawing complete as per specifications. - M30 (at 360Kg per cum coarse aggregate @ 0.69cum and fine aggregate @ 0.46cum)	Cum	6217.96	Rupees Six Thousand Two Hundred Seventeen And Paise Ninety Six Only
12	600.00	Vaccum de-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator, HOM of machinery, Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift.	Sqm	95.40	Rupees Ninety Five And Paise Forty Only
13	2235.25	Excavation for roadwork in soil with hydraulic excavator of 0.90 cum bucket capacity including cutting and loading in tippers, trimming bottom and side slopes, in accordance with requirements of lines, grades and cross sections, and transporting to embankment location and complete as per specifications. As per the direction of Engineer incharge	Cum	164.76	Rupees One Hundred Sixty Four And Paise Seventy Six Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
14	2085.25	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechaniqal mix plant carriage ' of mixed Material by tipper to site, laying in uniform layers with paver in sub- base/ base course on well prepared surface and compacting with vibratory roller to achieve the desired density.complete as per specifications. As per the direction of Engineer incharge	Cum	1768.08	Rupees One Thousand Seven Hundred Sixty Eight And Paise Eight Only
15	8341.00	Providing and applying primer coat with SS bitumen emulsion on prepared surface of granular Base such as WBM WMM including clearing of road surface and spraying primer at the rate of 0.60 kglsqm using mechanical means complete as per specifications. As per As per the direction of Engineer incharge	Sqm	27.56	Rupees Twenty Seven And Paise Fifty Six Only
16	25992.50	Providing and applying tack coat using 80/100 grade bitumen (VG10) on prepared black topped surfaces at 2.5 Kg per 10 sqm, heating bitumen in boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. As per the direction of Engineer incharge	Sqm	12.72	Rupees Twelve And Paise Seventy Two Only
17	513.10	Providing and laying dense bituminous macadam 50-75mm compacted thickness with 4.5% VG-30 Bitumen using 40/60 TPH capacity H.M.P, using crushed aggregates of grading II, premixed with VG 30 grade bituminous binder and transporting the hot mix to work site, laying with mechanical paver to the required grade level and alignment rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MORTH table 500-10, complete in all respects complete as per specification As per the direction of Engineer incharge	Cum	7120.02	Rupees Seven Thousand One Hundred Twenty And Paise Two Only
18	629.22	Providing and laying bituminous concrete 30-40 mm compacted thickness with VG30 Bitumen grade using 40-60 HMP using crushed aggregates of grading II, premixed with bituminous binder at 5.4% of mix and filler, transporting the hot mix to work site, laying with a mechanical paver finisher to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem rollers to achieve the desired compaction as per MoRT&H specification clause No. 500.9 complete in all respects as per specifications. As per the direction of Engineer incharge	Cum	8118.54	Rupees Eight Thousand One Hundred Eighteen And Paise Fifty Four Only
19	516.00	Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications. As per the direction of Engineer incharge	Sqm	542.72	Rupees Five Hundred Forty Two And Paise Seventy Two Only
20	850.68	Removing and resetting of footpath slab As per the direction of Engineer incharge	Sqm	132.50	Rupees One Hundred Thirty Two And Paise Fifty Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
21	413.28	Providing and fixing RCC Precast cover slab of 100mm thick for drain in cement concrete M20 using graded granite jelly 20mm and down size with steel reinforcement, including form work, lift charges, curing and concrete finished surfaces on both sides etc, complete and as per drawing and the directions of Engineer in-charge. As per the direction of Engineer incharge	Sqm	1738.00	Rupees One Thousand Seven Hundred Thirty Eight Only
22	1770.40	Removing and resetting of kerb stones As per the direction of Engineer incharge	Sqm	65.72	Rupees Sixty Five And Paise Seventy Two Only
23	2317.60	Providing and fixing pre cast solid cement concrete kerb stones made out of CC 1:2:4 with top and bottom width 114 and 165 mm respectively, 400mm high and 450mm in length finished with CM 1:3 plastering and finishing cutting including formwork, curing, including cost of materials, labour charges of machinery, loading and unloading, lead and lift, transportation ete.,complete. As per the direction of Engineer incharge	Sqm	331.78	Rupees Three Hundred Thirty One And Paise Seventy Eight Only
24	644.00	Painting two coats after filling the surface with synthetic enamel paint in approved shades on new plastered concrete surfaces, with materials, labour complete as per specifications.As per the direction of Engineer incharge	Sqm	63.60	Rupees Sixty Three And Paise Sixty Only
25	7082.50	Cleaning the existing black topped surface with brooms, soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatement including cost of all materials, labour, HOM of machineries complete as per specifications.As per the direction of Engineer incharge	Sqm	3.18	Rupees Three And Paise Eighteen Only
26	4.00	Geophysical investigation of site for sinking Borewell for supplying drinking water to the habitation either through the Hand pump, MWS of P.W.S.S by vertical electrical sounding by adopting Venner or Schlumberger's method, including reconnaissance survey of geological formation, Gerophysical investigation of existing Ground Wate in the vicinity, its qualityf 1.0 meter in consolidated formation for proper seating of casing pipe, depth of drilling required to cover full depth of aquifer proposed to be tapped, probable yield and other information required including transportation of instrument and accessories to work site., engaging technical personal and labour required etc., as per Specification and direction As per the direction of Engineer incharge	Each BW	1938.46	Rupees One Thousand Nine Hundred Thirty Eight And Paise Forty Six Only
27	200.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) 0 to 50 m As per the direction of Engineer incharge	Rmtr	315.18	Rupees Three Hundred Fifteen And Paise Eighteen Only

Executive Engineer
Project Division
Yelahanka Zone

Contractor

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
28	200.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) 50 to 1000 m As per the direction of Engineer incharge	Rmtr	412.00	Rupees Four Hundred Twelve Only
29	200.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) 100 to 150 m As per the direction of Engineer incharge	Rmtr	458.35	Rupees Four Hundred Fifty Eight And Paise Thirty Five Only
30	200.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,)150 to 200 m As per the direction of Engineer incharge	Rmtr	484.10	Rupees Four Hundred Eighty Four And Paise Ten Only
31	200.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) 200 to 250 m As per the direction of Engineer incharge	Rmtr	560.32	Rupees Five Hundred Sixty And Paise Thirty Two Only
32	200.00	Sinking borewell of 165 mm dia clear using super fast hydraulic rig of capacity 250 PSIG & above CFM & above in all strats including over burden upto 20 mts fixing of casing pipes, collars and cap with necessary cutting, throading and welding including transportation of rig and supporing vehicles, crew charges and cost of consumables etc., complete including yield testing at the final depth with a minimum working of compressor for one hour (excluding coat of casing pipes, collars, cap etc.,) 250 to 300 m As per the direction of Engineer incharge	Rmtr	600.49	Rupees Six Hundred And Paise Forty Nine Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
33	240.00	Supply of ISI mark 175 mm nominal bore, Plain end steel casing pipe - grade of Steel Fee 410 of wall thickness 5.4mm thick confirming to IS 4270:2001 and latest amendments, electric resistance welded steel tube material and confirming to IS 1387/1993 and manufactured by baseic open hearth electric or basic oxygen process in random length of 5 to 7 mts both ends threaded confirming tio IS 554/1985, one end fixied with socket confirming to IS 4270:2001 and the other end with screwed pipes ISI Marking weighing 25.10Kg/mtr (Inclusive of all taxes and durties) Prices include Collar-medium duty	Rmtr	1325.00	Rupees One Thousand Three Hundred Twenty Five Only
34	60.00	Providing 250mm dia PVC Pipe 6kg/cm As per the direction of Engineer incharge	Rmtr	1144.00	Rupees One Thousand One Hundred Forty Four Only
35	4.00	Providing and fixing 160mm Borewell Cap As per the direction of Engineer incharge	No	100.00	Rupees One Hundred Only
36	40.00	Providing MS Casing pipe collars As per the direction of Engineer incharge	Each	150.00	Rupees One Hundred Fifty Only
37	4.00	Supply and delivery at site brand New texmo/ innoval/ Lubi/ Sabar / Atalanta/ Calamal/ make suitable for vertical installation in 150mm dia bore well comprising of single stage or multistage CF pump close coupled by measns of stainless steel coupling to suitable HP suitable speed totally enclosed and filled with pure drinking water (Wet type) squirrel cage submersible induction motor suitable for opertation of 3PH., 50 Hz, 380/440 volts AC supply fitted with required aqccessories such as suction, casing suction strainers sand guard Non return value etc. complete . The pump and motor shall form an integral unit with all the required fittings 12.50 HP 25 stage. ATALANTA< SUGNA< CRI, KIRLOSKAR and other Equivalent Pumps 17.5 HP 30 Stage As per the direction of Engineer incharge	No	74300.00	Rupees Seventy Four Thousand Three Hundred Only
38	1220.00	Supplying of ISI marked galvanized mild steel tube (continously welded electric resistance welded (ERW) high frequency, induction welded (HFIW) Hot finished welded type of nominal bore given below screwed at both ends as per IS 554/1986 with latest amendments, pipes threaftes at one end and the other end protected asper specification in random lengths of 4 to 7 mtrs Confirming to IS 1239 part I/1990 with amendament 1-5 and with all its latest amendements if any. The pipes supplied should be with BIS mark No 3/08-09 2406/15.10.2008 As per the direction of Engineer incharge	Rmtr	525.30	Rupees Five Hundred Twenty Five And Paise Thirty Only
39	2400.00	Supplying and drawing 3 core flat PVC sheathed submersible pump cable manufactured with electrolytic grade copper with flexible copper with low resistance conductor confirming to table 3 class 5 of IS:8130-1984 and virgin grade PVC insulation and powder coating extruded PVC sheathed suitable for working voltage upto 1100Volts as per IS-694:1990 & confirming to GTP of GROUP-A. As per the direction of Engineer incharge	Mtr	188.70	Rupees One Hundred Eighty Eight And Paise Seventy Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
40	200.00	Labour charges for erection of new/ repaired submersible pumpset along with gi pipes inculding transportion each length pno 558 ino 3	No	88.00	Rupees Eighty Eight Only
41	4.00	Supplying and flush polished wood board with out front frount plank made of not less than 15mm thick plank after due groove cutting Finishing with necessary on fixing the same to the wall using tapered inverted wooden plugs screws etc.,	Each	302.00	Rupees Three Hundred Two Only
42	140.00	Supplying of 1.1 KV LT UG cable having aluminium condutor PVC insulated shethed, EXTREDED INNER SHEATHRD galvnised steel,stirp confirming IS 3975;1990 AND extruded PVC outer sheathing armoured cable IS 1554 part 1;1998 and confirming to GTP of group.	Mtr	140.40	Rupees One Hundred Forty And Paise Forty Only
43	140.00	Labour charges for laying of 1.1 K.V class UG cable,	Mtr	10.80	Rupees Ten And Paise Eighty Only
44	120.00	Digging or trenching of 0.6m deep x 0.5 mtr wide refilling the trench to the required ground level and consolidating etc.,	Mtr	117.00	Rupees One Hundred Seventeen Only
45	12.00	Supplying and fixing of Class A (meaium duty) GI pipe of wall thickness not less than 3.25mm on pole/wall/drain crossing with necessary clamping arrangements for UG cable of 1.1 KV class	Mtr	345.00	Rupees Three Hundred Forty Five Only
46	4.00	Supplying and fixing L.T. cast Iron pot head suitable for 1.1 KV class UG cable filled with necessary bituumen/insulating compound complete with terminals, clamps, bolts, nuts and washers etc.,	No	280.00	Rupees Two Hundred Eighty Only
47	4.00	Supplying, fixing, wiring, earth electrode for grounding conduits, I.C cutouts and other equipments on the meter board using 40 mm dia 2.90 mm thick GI pipe 2.5 m long buried in a pit. The pit should be filled with equal propotion of solt and charocoal 150 mm alround the pipe to complete depth. The connection from the pipe to the conduit etc., is to be established through GI wire of size, as per ISI specification 7.3.3 IS 732 using 12 mm dia bolts, nuts, washers and check nuts, etc., the pipe shall have 16 throught holes of 122 mm dia,	No.	2727.00	Rupees Two Thousand Seven Hundred Twenty Seven Only
48	12.00	Supplying and fixing of Porcelain fuse channel with cut out on existing wooden / panel using necessary nuts, bolts and washer etc., complete....	Each	360.00	Rupees Three Hundred Sixty Only
49	24.00	Supplying and fixing of heavy duty glands for ug cable 1.1 kv etc., complete....	Each	86.00	Rupees Eighty Six Only
50	24.00	Supplying and fixing of heavy duty glands for ug cable 1.1 kv etc., complete....	Each	86.00	Rupees Eighty Six Only
51	4.00	Supplying and fixing miniature circuit breakers/solaters on existing MCB distribution boards using necessary fixing materiasl wiring complete as requireds 5 to 32 amps triple pole with all lead and lift, loading, unloading and labour charges etc complete as per specifications	Each	1547.00	Rupees One Thousand Five Hundred Forty Seven Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
52	184000.00	Fabrication supplying and mounting MS box of 16 SWG suitable for floor /wall mounting, fully weather proof with provision for better heat dissipation, provided with hinged front cover, equipped with tamper proof locking arrangements, with suitable size clamps with necessary cable entry pipe with gland and box should be finished 2 coats of red oxide primer paint and finally finished with approved colour enamelled metal paint etc., complete box of 21600 sqcm	Sqcm	0.33	Rupees And Paise Thirty Three Only
53	4.00	Providing and fixing in position 50mm nominal bore gun metal non-return valve horizontal type of approved make including cost of all materials, labour and HOM of equipments with all leads complete as per specifications	No	1540.88	Rupees One Thousand Five Hundred Forty And Paise Eighty Eight Only
54	12.00	Providing NP/CP waste unions conforming to ISI specifications and fixing them in position as per directions including cost of materials, fixtures and conveyance to work spot etc., complete.	No	221.45	Rupees Two Hundred Twenty One And Paise Forty Five Only
55	12.00	Gate value 50 mm nominal bore gun metal	No	1650.00	Rupees One Thousand Six Hundred Fifty Only
56	4.00	NIPPLE 50 mm nominal bore gun metal	No	104.30	Rupees One Hundred Four And Paise Thirty Only
57	12.00	S BEND 50 mm nominal bore gun metal	No	219.00	Rupees Two Hundred Nineteen Only
58	4.00	TEE 50 mm nominal bore gun metal	No	169.00	Rupees One Hundred Sixty Nine Only
59	4.00	Supplying and delivery at site brand new star / Essen/ Lotus/Sun-shines/Adarsh/ GK Controls best indigenous make combined energy meter - cum- control panel board unit of size 600x450 x200 mm minimum mechanically strong vermin and water proof. The unit shall have two detachable doors suitable for operation on 3 ph, 50Hz, 380/440 volts, A.C supply with spring loaded latch, locking device with a key ribs should be provided inside the door, canopy apron and louvers ventilators shall be provided. the combined energy meter cum- control panel board unit suitable for operation. The panel board shall be fabricated on single unit in the above components for suitable pumpset.	No	10000.00	Rupees Ten Thousand Only
60	540.00	Earth work excavation for foundation of buildings, culverts, water supply, sanitary lines and electrical conduits either in pits or in trenches, 1.5m and above in width, in ordinary soil, exceeding 1.5m in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with all lead upto 50m after breaking of clods complete as per specifications	Cum	162.00	Rupees One Hundred Sixty Two Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
22/2/19

	Estimate Quantity	Item Name	Unit	Rates quoted by Sri. HONNAPPA MURTHY	
				Rate in figures	Rate in words
61	1200.00	Providing and installing at site of work pvc pipes including cost of pipes and special and labour including lowering into trenches laying true to line level and prefect linking at joints, leak proof including jointing of approved type with all labour and lift charges handling charges including encasing the pipes all round to a depth not less than 15 cms with gravel or selected earth available from the excavation etc. complete PVC pipe of 6kg/cm2 75 mm (0.662)	Mtr	132.00	Rupees One Hundred Thirty Two Only
62	540.00	Filling available excavated earth (excluding rock) in sides of foundations upto plinth in layers not exceeding 20 cms in depth, compacting each deposited layer by ramming after watering with a lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications	Each	95.00	Rupees Ninety Five Only
63	4.00	BESCOM Deposit	No	14000.00	Rupees Fourteen Thousand Only

Contractor

Executive Engineer
Project Division
Yelahanka Zone
22/2/19